#### Active Building RIBA Plan of Work Checklists Version 2.0, August 2020



#### Introduction


This document is part of a toolkit, providing checklists at each of the RIBA Work Stages to ensure design, delivery and operation of an Active Building.

#### **Purpose**

· Provide checklists to ensure Active Building principles have been considered at each stage in the project

The document should be read in conjunction with the following documents:

- RIBA Plan of Work 2020
- Active Building Design Guide
- · Active Building Code of Conduct
- · Active Building Project Template
- The Active Classroom Case Study
- The Active Office Case Study
- Active Building Technology Showcase
- Planning Policy Documents
- Approved Documents



 $\underline{\text{https://www.architecture.com/-/media/GatherContent/Test-resources-page/Additional-Documents/2020RIBAPlanofWorktemplatepdf.pdf} \\$ 

It is always recommended to use a collaborative procurement route for Active Building projects and to bring the whole Project Delivery Team together at the earliest possible stage in the project.

## 0 Strategic Definition

Core Tasks: Prepare Clients Requirements

Develop Business Case for feasible options including review of Project Risks and Project Budget

Ratify option that best delivers Client Requirements

Review Feedback from previous projects

Undertake Site Appraisals

Key Consideration	s for Active Building	Core Active Building Tasks	Done
<ul> <li>Client aspirations (level of 'Active')</li> <li>Desire for EV charging integration</li> </ul>		Review Active Building case studies, data and lessons learnt	20110
<ul> <li>Business case</li> <li>Whole Life Cost</li> </ul>	(WLC) considerations	Review Active Building Toolkit documents	
Site analysis - loc	cation, orientation,	Define Active Building requirements for project	
<ul><li>features</li><li>Planning Policy a</li></ul>	and local vernacular	Set objectives for Project Delivery Team	
Key stakeholders     Project Delivery Team	Identify key stakeholders		
Ensure Active Bu	ilding requirements are i	ncluded in all contractual documents related to the Active B project	uilding
Stage Outcome	The best means of achieving the Client Requirements confirmed		
Active Building Outcomes for Stage 0	<ul> <li>Level of Active Building agreed and written into the Project Brief for client sign off</li> <li>Agreement to share and publish monitoring data throughout the project, at design, construction and in use stages, to enable feedback</li> </ul>		
Information Exchanges	<ul> <li>Project Delivery Team – Active Building Toolkit</li> <li>Client Requirements – including Active Building Project Brief</li> <li>Business Case – including Active Building Business Case</li> </ul>		
Comments:	1		

# 0 Strategic Definition

Further information:	
Further information.	

#### 1 Preparation and Briefing

Core Tasks: Prepare Project Brief including Project Outcomes and Sustainability Outcomes, Quality

Aspirations and Spatial Requirements

Undertake Feasibility Studies

Agree Project Budget

Source Site Information including Site Surveys

Prepare Project Programme
Prepare Project Execution Plan

Key Consideration	ns for Active Building	Core Active Building Tasks	Done
<ul> <li>Feasibility: site features, orientation, potential to site environmental features of site</li> <li>Existing site infrastructure available</li> <li>Access to local energy networks</li> <li>Data capabilities of local networks</li> <li>Data monitoring requirements</li> </ul>		Develop feasibility study on proposed site(s), incorporating site analysis and constraints – financial, site, other	
		Develop high level data monitoring and performance specifications	
		Arrange early stakeholder engagement sessions	
Performance spe	ecifications	Start photographic record	
<ul> <li>Scope for renewable energy generation on site</li> <li>Types of energy storage</li> <li>Types of EVs anticipated for use (may be linked to building type and occupancy)</li> </ul>		Utilise appropriate design tools, such as Passive House Planning Package (PHPP) and Good Homes Alliance (GHA) Overheating tool (for new homes) in early design decision making	
linked to building	type and occupancy)	Identify options for renewable energy generation	
		Identify potential energy storage technologies for heat and electricity	
		Identify potential locations for EV charging facilities	
		Identify options for linking to local and national energy networks	
Ensure Active Bu	ilding requirements are i	ncluded in all contractual documents related to the Active B project	uilding
Stage Outcome	Project Brief approved b	by the client and confirmed that it can be accommodated on the s	site
Active Building Outcomes for Stage 1	<ul> <li>Client approval to develop project to be an Active Building</li> <li>Level of Active Building agreed</li> </ul>		
Information Exchanges	<ul> <li>Feasibility Studies – including Active Building Energy Strategy &amp; Site Analysis</li> <li>Site Information</li> <li>Project Budget – including uplift for Active Building measures and early LCC Report</li> <li>Project Programme</li> <li>Procurement Strategy – collaborative route suggested with early contractor engagement</li> <li>Early LCA</li> <li>Responsibility Matrix</li> <li>Information Requirements</li> </ul>		

## 1 Preparation and Briefing

Comments:	
Further information:	

# 2 Concept Design

Core Tasks: Prepare Architectural Concept incorporating Strategic Engineering requirements and aligned to

Cost Plan, Project Strategies and Outline Specification

Agree Project Brief Derogations

Undertake Design Reviews with client and Project Stakeholders

Prepare stage **Design Programme** 

Key Consideration	s for Active Building	Core Active Building Tasks	Done
<ul> <li>Building form factor</li> <li>Site positioning</li> <li>Locations of incoming services</li> <li>Construction methods and materials – Life Cycle Assessment (LCA) considerations</li> <li>Energy Strategy</li> <li>Renewable energy generation capacity</li> <li>Available generation surfaces – building and site wide</li> <li>Optimum energy storage capacity</li> <li>Life Cycle Costing (LCC)</li> <li>Provision of green infrastructure to reduce run-off and provide biodiversity</li> <li>Spatial requirements for EV charging bays, adjacent to suitable infrastructure</li> </ul>		Develop simple massing model and initial energy model based on early design scheme(s) to determine predicted energy consumption and generation	
		Develop a report on early design(s) and recommendations for steps to enable Active Building elements	
		Prepare information to support early Life Cycle Costing (LCC) to support the aim to reduce whole life costs and to aid decision making on specifications	
		Collate information on Active Building technologies to support the Design and Access statement (DAS) for planning application	
		From site analysis, identify optimum site position for building in relation to site features and energy generation	
<ul><li>where possible</li><li>Types of EV cha</li></ul>	rging facilities required,	Use outputs from energy model to determine optimum size of energy storage systems for both heat and electricity	
e.g. for e-bikes, e-scooters, e-cars, e-vans, e-buses	Design for EV integration, including charging facilities, e-bike storage shelters, PV parking canopies		
		Determine electricity network connection locations and positioning of data hub	
Ensure Active Bu	illding requirements are i	ncluded in all contractual documents related to the Active B project	uilding
Stage Outcome	Architectural Concept	approved by the client and aligned to the <b>Project Brief</b>	
Active Building Outcomes for Stage 2	<ul> <li>Active Building elements approved by client</li> <li>Active Building Strategy developed</li> </ul>		
Information Exchanges	<ul> <li>Project Brief Derogations</li> <li>Signed off Stage Report – including Active Building Assessment</li> <li>Project Strategies</li> <li>Outline Specifications – including Active Building technologies and early LCA considerations</li> <li>Cost Plan – including early LCC Report</li> <li>Initial massing and energy models</li> </ul>		

# 2 Concept Design

Comments:	
Further information:	

## 3 Spatial Coordination

Core Tasks: Undertake Design Studies, Engineering Analysis and Cost Exercise to test Architectural Concept

resulting in Spatially Coordinated design aligned to updated Cost Plan, Project

Strategies and Outline Specification

Initiate Change Control Procedures
Prepare stage Design Programme

Key Consideration	ns for Active Building	Core Active Building Tasks	Done
energy loads cre	based on the reduced eated through building	Use evidence from concept model to determine options for renewable energy generation technologies	
<ul><li>fabric and passi</li><li>Renewable ene</li></ul>	ve design rgy strategy – is it possible	Identify predicted energy loads versus generation capacity	
to generate mor	e than consumed? Can	Develop an energy strategy	
generation surfa	n be adapted to increase aces if needed?	Develop performance specifications for an Active Building	
	nents for energy storage eir integration with	Undertake early LCA and LCC	
equipment used	for heating, ventilation,	Design for adaptability – spatial and building services	
<ul> <li>cooling, vertical circulation, lighting and small power</li> <li>Spatial requirements and landscape features associated with EVs</li> <li>Spatial and power requirements for data monitoring and communication systems</li> </ul>		Establish potential energy generation sources and capacity of energy storage required. Determine spatial requirements, including ancillary equipment (such as inverters, charge controllers, meters). Consider access to energy storage for ongoing maintenance	
monitoring and communication systems	Determine number and type of EV charging facilities required depending on client aspirations and building occupancy		
		Start developing software to enable communication between the BMS and the grid to enable smart export and import regimes to be implemented	
		Ensure tendering contractors understand Active Building concepts and how to achieve Active Building requirements	
Ensure Active	Building are included in a	all contractual documents related to the Active Building pro	ject
Stage Outcome	Architectural and engineer	ring information Spatially Coordinated	
Active Building Outcomes for Stage 3	Active Building technol	ogies incorporated	
Information Exchanges	Updated Cost Plan	fications - including Active Building technologies including Active Building Energy Strategy	

# 3 Spatial Coordination

Comments:		
Further information:		

## 4 Technical Design

Core Tasks: Develop architectural and engineering technical design

Prepare and coordinate design team Building Systems information

Prepare and integrate specialist subcontractor **Building Systems** information

Prepare stage **Design Programme** 

Key Consideration	s for Active Building	Core Active Building Tasks	Done
<ul> <li>Specification of materials – LCA considerations</li> <li>Form of construction</li> <li>Use of local resources</li> <li>Specifications of technologies and systems</li> <li>Specifications of energy generation technologies and assessment of their</li> </ul>		Develop detailed building physics/dynamic thermal model	
		Review design information and Mechanical, Electrical and Plumbing (MEP) strategy	
		Review technical specifications developed to ensure Active Building technologies included – assess equipment required to suit the energy generation and storage, and incorporate into the energy strategy.	
<ul> <li>Specifications of and their integral</li> </ul>	n other building services energy storage systems tion with the energy	Consider most appropriate types of energy storage (heat and electrical)	
	ipment used for heating, ng, vertical circulation,	Review specifications against LCA and LCC criteria	
lighting and sma	ll power	Develop data monitoring specifications	
	EV charging facilities communication and	Ensure use of Active Building naming schema for BMS	
monitoring system		Develop a control strategy for EV integration into the BMS	
		Specify control systems to enable controlled interaction of energy with local and national grid networks	
Ensure Active Bu	ilding requirements are i	ncluded in all contractual documents related to the Active B project	uilding
Stage Outcome	All design information re	quired to manufacture and construct the project completed	
Active Building Outcomes for Stage 4	<ul> <li>All information on Active Building technologies incorporated into design information</li> <li>Active Building data monitoring specifications developed</li> </ul>		
Information Exchanges	<ul> <li>Manufacturing Information</li> <li>Construction Information</li> <li>Final Specifications – including Active Building Data Monitoring Specification</li> <li>Residual Project Strategies</li> <li>Building Regulations Application</li> <li>Active Building Report based on energy modelling</li> <li>Active Building Information Pack for toolbox talks</li> </ul>		

# 4 Technical Design

Comments:	
Comments.	
Foodbase to foods and	
Further information:	
rurther information:	
Further information:	
Further information:	
Further information:	

## 5 Manufacturing and Construction

Core Tasks: Finalise Site Logistics

Manufacture Building Systems and construct building

Monitor progress against Construction Programme

Inspect Construction Quality

Resolve Site Queries as required

Undertake Commissioning of building

Prepare Building Material

Key Consideration	ns for Active Building	Core Active Building Tasks	Done
<ul> <li>Thermal performance of fabric, potential for thermal bridging and level of airtightness</li> <li>Retention of low embodied carbon materials and construction techniques</li> <li>Use of local resources and labour where</li> </ul>		Deliver Active Building toolbox talks for in-factory and on-site inductions, management and commissioning	
		Undertake regular site inspections to ensure the delivery of an Active Building, including thermography and air-tightness tests	
	on and commissioning of enewable energy	Document installation of technologies and equipment, including site photographs	
technologies and to ensure building	d energy storage systems ag performs as designed	Ensure BMS installer has and uses Active Building naming schema, and all necessary monitoring is in place	
	on and commissioning of ipment to enable ing regimes	Ensure correct installation of MEP equipment aligned with Active Building philosophy	
controlled onling	ing regimes	Ensure smart charging facilities are incorporated to enable optimised control	
		Ensure rigorous commissioning and testing to ensure all systems are performing as per the design intent, before building is signed off and handed over	
		Ensure building is connected to local and national grid networks in a manner to enable controlled import and export of energy	
Ensure Active Bu	uilding requirements are in	ncluded in all contractual documents related to the Active Br project	uilding
Stage Outcome	Manufacturing, construction and Commissioning completed		
Active Building Outcomes at Stage 5	<ul> <li>Active Building training completed</li> <li>Active Building technologies installed and commissioned</li> </ul>		
Information Exchanges	<ul> <li>Building Manual including Health and Safety File and Fire Safety Information – plus information on Active Building technologies and Data Monitoring Strategy</li> <li>Practical Completion certificate including Defects List</li> <li>Asset Information</li> </ul>		ormation

## 5 Manufacturing and Construction

Comments:	
Further information:	
rurmer information:	

#### 6 Handover

Core Tasks: Hand over building in line with Plan for Use Strategy

Undertake review of Project Performance

Undertake seasonal Commissioning

Rectify defects

Complete initial Aftercare tasks including light touch Post Occupancy Evaluation

Key Consideration	ns for Active Building	Core Active Building Tasks	Done
Information for b	ouilding user manual	Provide information for Operation & Maintenance (O & M) manuals, including detailed information on:  • the construction materials and methods  • building services  • renewable energy technologies and associated equipment  • energy storage systems, including instructions for shutting down the energy storage system, in the case of emergency or to undertake maintenance  • EV charging systems  • control systems  • monitoring regimes  Include clear diagrams  Review the whole design and construction process with Project Delivery Team and capture lessons learnt  Undertake post-project review workshop with all stakeholders	
		Deliver handover workshops with building owners/occupiers/Facilities Management Team (FMT)	
Ensure Active Building requirements are included in all contractual documents related to the Active Building project			
Stage Outcome	Building handed over, Aftercare initiated and Building Contract concluded		
Active Building Outcomes for Stage 6	<ul> <li>Active Building user manual completed</li> <li>Active Building data monitoring in place for optimised building operation, planned maintenance regimes, and predictive control strategies</li> </ul>		
Information Exchanges	<ul> <li>Feedback on Project Performance – Post Project Review, including Lessons Learnt</li> <li>Final Certificate</li> <li>Feedback from light touch Post Occupancy Evaluation (POE)</li> <li>Building User Handbook</li> </ul>		

## 6 Handover

Comments:	
Further information:	

Core Tasks: Implement Facilities Management and Asset Management

Undertake Post Occupancy Evaluation of building performance in use

Verify Project Outcomes including Sustainability Outcomes

Key Considerati	ons for Active Building	Core Active Building Tasks	Done	
<ul> <li>Building Performance Evaluation (BPE)</li> <li>Post Occupancy Evaluation (POE)</li> <li>Impacts of adaptations, renovations, fit-out</li> <li>Optimisation of systems</li> </ul>	Undertake BPE using installed monitoring equipment			
	Capture data in Active Building database and assess optimised performance of systems			
		Ensure O & M and building user manuals are kept up-to-date as necessary		
		Undertake Whole Life Cost reporting, based on LCC report, cost savings and any income generated from the sharing of energy with local and national grid networks		
		Develop/determine POE assessment method and undertake POE with building users and FMT		
	Ensure generation technologies are working effectively.  Monitor generation against consumption – identify any unanticipated discrepancies and resolve			
	Ensure energy storage systems are working effectively.			
	Develop predictive control strategies to optimise use of energy storage in conjunction with energy generation and consumption, and electric vehicle charging			
	Ensure EV charging systems and controls are working effectively			
		Develop planned maintenance regimes to ensure technologies and equipment are working optimally		
Ensure Active Building requirements are included in all contractual documents related to the Active Building project				
Stage Outcome	Building used, operated and maintained efficiently			
Active Building Outcomes for Stage 7	<ul> <li>Active Building data monitoring is working effectively</li> <li>Active Building technology is monitored and adapted as needed</li> </ul>			
Information Exchanges	<ul> <li>Feedback from Post Occupancy Evaluation (POE)</li> <li>Updated Building Manual including Health and Safety File and Fire Safety Information</li> <li>Life Cycle Cost (LCC) Report</li> <li>Life Cycle Analysis (LCA) Report</li> <li>Updated Active Building Database</li> </ul>			

## 7 Use

Comments:	
Further information:	